



Forsyth County Procurement

Donna H. Kukarola, CPPO, CPPB, Director

August 24, 2021

ADDENDUM #1

Bid 21-115-3150

For: Providing all materials, equipment, inside wide bands, and labor to install the pipe liners and grout the existing 84" CMP "B" and existing 72" CMP "A" on Chamonix Drive just south of SR 20. Both crossings A & B are in a live stream tributary to Daves Creek. Access will be provided within the right of way, with the County clearing out trees over the storm drain from end to end as needed.

This addendum supersedes and supplements all portions of the bidding documents and becomes part of the contract documents for the above-referenced project.

Where any item called for in the specifications or indicated on the drawings is supplemented hereby, the original requirements shall remain in effect.

Where any original item is amended, voided or superseded hereby, the provision of such item not so specifically amended, voided or superseded shall remain in effect.

Response to questions received: *(response in italics)*

1. May Profile Wall HDPE meeting ASTM F-894 also be a liner of choice to reline these pipes?
The pipe lining material submitted is mostly used for sewer/water line applications. The liner provides a 50-year life (the liner specified has a 75-year life). The liner information states minimum inside diameter of the existing culvert should be 72" diameter. Thus this would not be considered an equivalent alternate.
2. May CTR Coatings/OBIC Products we considered?
No, this is a coating and is not structural so is not an equivalent alternate.

End of Addendum #1