

# GDOT Earthwork Volumes Report

Report Created: 2/23/2022  
Time: 2:52pm

**Cross Section Set Name:** DE20

**Alignment Name:** DE20

**Input Grid Factor:** 1.000000 **Note:** All units in this report are in feet, square feet and cubic yards unless specified otherwise.

----- Station Quantities -----

Baseline Station	----- Cut -----				----- Fill -----				Mass Ordinate
	Factor	Area	Volume	Adjusted	Factor	Area	Volume	Adjusted	
72+54.64	1.000	0.000	0.000	0.000	1.000	0.000	0.000	0.000	0.000
73+00.00	1.000	38.199	32.086	32.086	1.000	0.627	0.526	0.526	31.559
73+50.00	1.000	26.653	60.048	60.048	1.000	5.147	5.346	5.346	86.261
74+00.00	1.000	2.715	27.192	27.192	1.000	34.587	36.790	36.790	76.663
74+25.09									0.000
74+50.00	1.000	1.347	3.761	3.761	1.000	134.452	156.517	156.517	-76.094
75+00.00	1.000	11.932	12.295	12.295	1.000	30.969	153.168	153.168	-216.966
75+50.00	1.000	25.356	34.526	34.526	1.000	13.502	41.177	41.177	-223.617
76+00.00	1.000	63.402	82.184	82.184	1.000	0.015	12.516	12.516	-153.950
76+50.00	1.000	0.000	58.706	58.706	1.000	0.000	0.014	0.014	-95.258
77+00.00	1.000	0.000	0.000	0.000	1.000	0.000	0.000	0.000	-95.258
77+50.00	1.000	0.000	0.000	0.000	1.000	0.000	0.000	0.000	-95.258
78+00.00	1.000	0.000	0.000	0.000	1.000	0.000	0.000	0.000	-95.258
78+50.00	1.000	0.000	0.000	0.000	1.000	0.000	0.000	0.000	-95.258
78+92.82	1.000	0.000	0.000	0.000	1.000	0.000	0.000	0.000	-95.258
Grand Total:			310.797	310.797			406.055	406.055	