

GDOT Earthwork Volumes Report

Report Created: 2/23/2022
Time: 3:10pm

Cross Section Set Name: DE9_2

Alignment Name: DE9

Input Grid Factor: 1.000000 **Note:** All units in this report are in feet, square feet and cubic yards unless specified otherwise.

----- Station Quantities -----

Baseline Station	Factor	Cut				Fill				Mass Ordinate
		Area	Volume	Adjusted	Factor	Area	Volume	Adjusted		
57+90.28	1.000	0.000	0.000	0.000	1.000	0.000	0.000	0.000	0.000	0.000
58+00.00	1.000	0.000	0.000	0.000	1.000	0.000	0.000	0.000	0.000	0.000
58+50.00	1.000	0.000	0.000	0.000	1.000	0.000	0.000	0.000	0.000	0.000
59+00.00	1.000	3.800	3.519	3.519	1.000	3.212	2.974	2.974	0.544	
59+50.00	1.000	86.788	83.878	83.878	1.000	1.072	3.967	3.967	80.456	
60+00.00	1.000	17.377	96.449	96.449	1.000	25.827	24.907	24.907	151.998	
60+50.00	1.000	216.154	216.232	216.232	1.000	0.496	24.374	24.374	343.856	
61+00.00	1.000	17.427	216.278	216.278	1.000	55.835	52.159	52.159	507.975	
61+50.00	1.000	29.257	43.226	43.226	1.000	40.471	89.172	89.172	462.029	
62+00.00	1.000	64.870	87.155	87.155	1.000	2.419	39.713	39.713	509.471	
62+50.00	1.000	80.049	134.185	134.185	1.000	1.959	4.054	4.054	639.601	
63+00.00	1.000	86.742	154.436	154.436	1.000	4.336	5.829	5.829	788.209	
63+50.00	1.000	96.459	169.631	169.631	1.000	0.146	4.149	4.149	953.690	
64+00.00	1.000	78.180	161.703	161.703	1.000	0.378	0.485	0.485	1114.908	
64+28.43	1.000	67.567	76.733	76.733	1.000	3.157	1.861	1.861	1189.780	
Grand Total:			1443.425	1443.425			253.644	253.644		