



Forsyth County Procurement

Greg Bridges, Procurement Agent III

September 1, 2021

ADDENDUM #2

Bid 21-115-3150

For: Providing all materials, equipment, inside wide bands, and labor to install the pipe liners and grout the existing 84" CMP "B" and existing 72" CMP "A" on Chamonix Drive just south of SR 20. Both crossings A & B are in a live stream tributary to Daves Creek. Access will be provided within the right of way, with the County clearing out trees over the storm drain from end to end as needed.

This addendum supersedes and supplements all portions of the bidding documents and becomes part of the contract documents for the above-referenced project.

Where any item called for in the specifications or indicated on the drawings is supplemented hereby, the original requirements shall remain in effect.

Where any original item is amended, voided or superseded hereby, the provision of such item not so specifically amended, voided or superseded shall remain in effect.

Response to questions received and Revised Bid Schedule:

1. Q: The Profile Wall HDPE meeting ASTM F-894 has a 100 year design life. It is used in multiple states, including Georgia, to reline failing CMP and RCP culvert pipes. May this pipe be reconsidered as an acceptable alternate?
A: *Solid wall HDPE pipe can be considered as alternate for the ultra flo Pipe bid in size for size match.*
2. Q: What are the Traffic Control Requirements?
A: *As required for lane closures, shoulder closures, as outlined in the current edition of the Uniform Manual on Traffic Control Devices.*
3. Q: will the County be responsible for moving the pipe debris downstream from Location B?
A: *Yes, the County will remove the pipe debris before work begins.*
4. Q: Will the County be able to re-measure and confirm the size requirements of both pipes?
A: *Pipes have been re-measured and existing pipe sizes are correctly shown in bid.*

Revised Bid Schedule including Schedule to Complete:

BID SCHEDULE 21-115-5211

FOR: Providing all materials, equipment, inside wide bands, and labor to install the pipe liners and grout the existing 84" CMP "B" and existing 72" CMP "A" on Chamonix Drive just south of SR 20. Both crossings A & B are in a live stream tributary to Daves Creek. Access will be provided within the right of way, with the County clearing out trees over the storm drain from end to end as needed.

Bid prices shall include all labor, materials, bailing, shoring, removal, overhead (Direct and Indirect), profit, insurance, bonds, and other costs, to cover finished Work of the several kinds called for.

Bidder accepts terms and conditions contained in Bid Document Package including, without limitation, those dealing with Owner's time for accepting Bid and disposition of Bid Security.

Bidder has examined site and locality where the Work is to be performed and legal requirements (federal, state, and local laws, ordinances, rules, and regulations) and conditions affecting Work cost, difficulty, progress, or performance and has made independent investigations as Bidder deems necessary. Bidder has given Owner written notice concerning conflicts, errors, or discrepancies discovered in Bid Document Package and written resolution by Owner is acceptable to Bidder.

	ITEM	UNIT COST	TOTAL
1	Traffic Control	Lump Sum	\$
2	Erosion Control	Lump Sum	\$
3	Grout Fill, 100 CY	\$ CY	\$
4	Location B; Provide 100 Ft. Contech Ultra Flo Pipe AL T2 LS 12 GA, 78" diameter, skid rails, 4 grout ports every 20' LF, Wide Internal Bands/flat gaskets.	\$ LF	\$
5	Location A; Provide 90 Ft. Contech Ultra Flo Pipe AL T2 LS 12 GA, 66" diameter, skid rails, 4 grout ports every 20' LF, Wide Internal Bands/flat gaskets.	\$ LF	\$

	TOTAL		\$

Total Bid(in written form): _____

Schedule to Complete (days): _____

Authorized Signature: _____ Date: _____

Printed Name and Title: _____

Company Name: _____