



Forsyth County Procurement

Tyra Little, Procurement Agent III

October 1, 2021

ADDENDUM #2

Bid 21-124-3300 Dick Creek Sanitary Sewer & Pump Station

For: Furnish all labor, equipment, and materials necessary to Lower Dick Creek Sanitary Sewer and Pump Station Phase-Out Project, located in southeast Forsyth County along Dick Creek between St. Marlo Pumping Station and Old Atlanta Road.

The project phases out and demolishes an existing pump station and installs new sewer which consists of 80 feet of 8-inch DIP, 280 feet of 12-inch DIP, 2,611 feet of 18-inch DIP, 14 Manholes, and 330 feet of steel casing pipe.

This addendum supersedes and supplements all portions of the quote documents and becomes part of the quote documents for the above-referenced project.

Where any item called for in the specifications or indicated on the drawings is supplemented hereby, the original requirements shall remain in effect.

Where any original item is amended, voided, or superseded hereby, the provision of such item not so specifically amended, voided, or superseded shall remain in effect.

QUESTIONS/ANSWERS (*answers in italics*)

1. US Pipe does not make 8" and 12" in class 250 P401 and Zinc coating, but they do make the 18" in class 250 with those coatings. The smaller diameter, 8" & 12" is made in a minimum for class 350 with those coatings.

Section 333113 SANITARY UTILITY GRAVITY SEWER allows class 350 pipe to be supplied but does not require class 250 pipe. Interior coatings must be PROTECTO 401™ Cerami Epoxy and the exterior of the pipe shall be coated with Zinc before the bituminous coating is applied. Class 350 8" and 12" DIP with interior and exterior coating is acceptable. Class 250 is required for 18" DIP with coatings.

2. Will there be any access allowed from St. Marlo Fairway Drive ? or is the only access from Old Atlanta Road?

FCDWS owns the St. Marlo Pump Station property and therefore has access rights across St. Marlo's private streets. Damage to St. Marlo's streets is the Contractor's responsibility. FCDWS will arrange use of the streets during construction.

3. The bid form has a mobilization allowance set for \$80,000, but the Measurement and Payment says Mobilization not to exceed 10% of Bid. Which one is correct?
Mobilization allowance is set to \$80,000.
4. What size and how long is the existing force main out of St. Marlo Pump Station to be grouted?
A minimum of 20 feet.

Is this work to be included in Item 117?

Yes

5. I know there is a Rock Excavation Pay Item, but is there a Geotechnical Report that is available? it would be helpful I for location of rock, surveys and monitoring of blasting required.
The soils report has been placed on the bid site for the contractor's review.

The geotechnical report can be obtained from our FTP site

<https://file-010.troposphere.info/index.php/s/5WtwPFdpf4wH4sg>

END OF ADDENDUM #2