

GDOT Earthwork Volumes Report

Report Created: 2/23/2022
Time: 2:47pm

Cross Section Set Name: DE18

Alignment Name: DE18

Input Grid Factor: 1.000000 **Note:** All units in this report are in feet, square feet and cubic yards unless specified otherwise.

----- Station Quantities -----

Baseline Station	Factor	Cut				Fill				Mass Ordinate
		Area	Volume	Adjusted	Factor	Area	Volume	Adjusted		
51+62.09	1.000	0.000	0.000	0.000	1.000	0.000	0.000	0.000	0.000	0.000
52+00.00	1.000	0.000	0.000	0.000	1.000	0.000	0.000	0.000	0.000	0.000
52+50.00	1.000	0.000	0.000	0.000	1.000	0.000	0.000	0.000	0.000	0.000
53+00.00	1.000	0.000	0.000	0.000	1.000	0.000	0.000	0.000	0.000	0.000
53+50.00	1.000	87.708	81.211	81.211	1.000	9.761	9.038	9.038	72.173	
54+00.00	1.000	156.722	226.324	226.324	1.000	1.107	10.063	10.063	288.433	
54+50.00	1.000	98.066	235.915	235.915	1.000	4.869	5.533	5.533	518.815	
55+00.00	1.000	2.637	93.243	93.243	1.000	23.976	26.708	26.708	585.350	
55+50.00	1.000	88.625	84.501	84.501	1.000	19.440	40.200	40.200	629.651	
56+00.00	1.000	107.653	181.739	181.739	1.000	13.442	30.446	30.446	780.943	
56+50.00	1.000	92.895	185.693	185.693	1.000	11.790	23.363	23.363	943.274	
57+00.00	1.000	77.933	158.174	158.174	1.000	6.984	17.383	17.383	1084.065	
57+50.00	1.000	55.893	123.912	123.912	1.000	0.148	6.603	6.603	1201.373	
58+00.00	1.000	18.462	68.847	68.847	1.000	3.698	3.562	3.562	1266.659	
58+50.00	1.000	36.864	51.228	51.228	1.000	0.000	3.424	3.424	1314.462	
59+00.00	1.000	21.617	54.149	54.149	1.000	0.836	0.774	0.774	1367.838	
59+47.35	1.000	6.169	24.364	24.364	1.000	6.579	6.502	6.502	1385.700	
Grand Total:			1569.299	1569.299			183.600	183.600		