GDOT Earthwork Volumes Report

Report Created: 2/23/2022
Time: 2:54pm

Cross Section Set Name: DE205

Alignment Name: DE205

Input Grid Factor: 1.000000 **Note:** All units in this report are in feet, square feet and cubic yards unless specified otherwise.

	- - - - - - - - - - - - - - - - Station Quantities - - - - - - - - - - - - - - - -								
	- - - - - - - - - - Cut - - - - - - - - - -				- - - - - - - - - - Fill - - - - - - - - - -				
Baseline Station	**Factor**	**Area**	**Volume**	**Adjusted**	**Factor**	**Area**	**Volume**	**Adjusted**	**Mass Ordinate**
3+74.61	1.000	0.000	0.000	0.000	1.000	0.000	0.000	0.000	0.000
4+00.00	1.000	0.000	0.000	0.000	1.000	0.000	0.000	0.000	0.000
4+50.00	1.000	0.000	0.000	0.000	1.000	0.000	0.000	0.000	0.000
5+00.00	1.000	0.000	0.000	0.000	1.000	0.000	0.000	0.000	0.000
5+50.00	1.000	0.000	0.000	0.000	1.000	0.000	0.000	0.000	0.000
6+00.00	1.000	0.000	0.000	0.000	1.000	0.000	0.000	0.000	0.000
6+50.00	1.000	0.000	0.000	0.000	1.000	0.000	0.000	0.000	0.000
7+00.00	1.000	0.000	0.000	0.000	1.000	0.000	0.000	0.000	0.000
7+50.00	1.000	0.000	0.000	0.000	1.000	0.000	0.000	0.000	0.000
8+00.00	1.000	27.064	25.059	25.059	1.000	0.584	0.541	0.541	24.518
8+50.00	1.000	69.523	89.432	89.432	1.000	0.000	0.541	0.541	113.409
9+00.00	1.000	127.305	182.248	182.248	1.000	0.000	0.001	0.001	295.656
9+50.00	1.000	169.456	274.779	274.779	1.000	0.000	0.000	0.000	570.434
10+00.00	1.000	195.997	338.383	338.383	1.000	0.000	0.000	0.000	908.817
10+50.00	1.000	221.873	386.917	386.917	1.000	0.000	0.000	0.000	1295.734
11+00.00	1.000	197.627	388.426	388.426	1.000	0.000	0.000	0.000	1684.160
11+50.00	1.000	137.214	310.038	310.038	1.000	0.000	0.000	0.000	1994.197
11+92.20	1.000	0.000	107.231	107.231	1.000	0.000	0.000	0.000	2101.429
Grand Total:			2102.512	2102.512			1.083	1.083	